



STORMWATER CONCRETE CHANNEL WITH FLOW NET FOR S 5-1 - S 5-6



CONSTRUCTION JOINT NTS



EXPANSION JOINT (EJ)

- ALL REINFORCEMENT TO BE APPROVED BY THE
- ENGINEER PRIOR TO CASTING OF CONCRETE REF 395 TO BE PLACED IN THE MIDDLE OF THE
- CONCRETE
- CONCRETE
 CONCRETE STRENGTH REQUIREMENTS AT 28 DAYS
 IS 25MPa
 7 AND 28 DAY CONCRETE CUBE TEST RESULTS TO
- BE SUBMITTED TO ENGINEER
 ALL EXPOSED SHARP EDGES ABOVE GROUND
- LEVEL TO HAVE 10 X 10mm CHAMFERS
 MAXIMUM SIZE OF COARSE AGGREGATE TO BE
 19mm
 CONCRETE FINISHES TO HAVE A SMOOTH WOOD
- FLOATED FINISH
 TO BE CONSTRUCTED IN ACCORDANCE WITH
- SANS 1200 G (CONCRETE : STRUCTURAL)
 BACKFILLING SHALL COMMENCE ONLY AFTER
 THE CONCRETE HAS ATTAINED THE
 28 DAYS COMPRESSIVE STRENGTH.

- 28 DAYS COMPRESSIVE STRENGTH.

 9. BACKFIL TO 90% MOD AASHTO DENSITY IN
 LAYERS NOT EXCEEDING 300mm WITH APPROVED
 GRANULAR MATERIA.

 10. CONSTRUCTION JOINTS (C.) TO BE INSTALLED AT
 EVERY 3" AND EXPANSION JOINT (E.) EVERY 12m

 11. CONCRETE WILL BE WELL VIBRATED TO
 ELIMINATE CAVITIES OR HONEYCOMBING.
 UNFORMED HORIZONTAL SURFACES (TOP OF ONFORMED HORIZONIAL SURFACES (TOP OF CONCRETE) WILL BE FLOATED WITH A WOODEN TROWEL TO RENDER A UNIFORM, SKID RESISTANT, HORIZONIAL SURFACE.

 12. ALL LEVELS TO BE CHECKED AND VERIFIED PRIOR TO CONSTRUCTION WORK COMMENCES

 13. ALL WORK WUST BE DONE IN ACCORDANCE WITH SANST200.

EFERENCE / VERWYSINGS RUSTENBURG CIVILCONSULT Tel 012 343 6297 / 0845 PO BOX 12645 HATFIELD 0028 Fax 012 343 8929 / 086 583 624 mail@civilconsult.co.za G.F.J. RAS J. DAVEL G.F.J. RAS CHECKED ROJECT / PROJEK RAFFREDI

RAWING TITLE / TEKENINGTITEL

MATE: JULY 2024 1:2000

3328/550/01/00 TIENT DWG NO KLIENT TEK NR

CONCRETE CHANNEL DETAIL AND FLOW DRAIN

LE NO. Left NR.